U.S. ARMY CORPS OF ENGINEERS

ILLINOIS WATERWAY

MISSISSIPPI VALLEY DIVISION
GREAT LAKES & OHIO RIVER DIVISION

ROMEOVILLE

WOODRIDGE

LEMONT

41°40'00" N

41°41'00" N

41°39'00" N

88°04'00" W

88°03'00" W

88°02'00" W

1

Channel Span

I-355 Highway Bridge
Horizontal Clearance: 160.0 ft
Vertical Clearance above Pool Stage: 74.9 ft
Low Steel Elevation: 652.4 ft

Quarry

SAFETY & SECURITY ZONE
RIVER MILES 296.0 - 296.7
SUBMERGED ELECTRIC BARRIER
(FISH BARRIER)

DES PLAINES RIVER

297

298

299

158 SCARPELLI MATERIALS, INC. TERMINAL #301

159 CITGO PETROLEUM CORP. LEMONT

160 KORALL CORP LEMONT ASPHALT DOCK

161 NORAMCO - CHICAGO

162 KAISER LEMONT WHARF

163 NUCOR-LEMONT, WHARF

164 ARTCO, LEMONT SLIP NO. 1

165 ILLINOIS MARINE TOWING, LEMONT SLIP NO. 2 STEEL-UNLOADING WHARF

157 UNOCOL COAL DOCK

V. Clr. 72.4 ft

CHICAGO SHIP & SANITARY CANAL

ILLINOIS & MICHIGAN CANAL (ABANDONED)

SLIP 1

SLIP 2

2

Channel Span

Enbridge Energy Pipeline
Horizontal Clearance: 160 ft
Vertical Clearance above Pool Stage: 42.2 ft
Low Steel Elevation: 620.2 ft

MATCH LINE CHART 99

MATCH LINE CHART 101

WILL COUNTY
COOK COUNTY

355

2013

BUOY POSITIONS ON CHART ARE APPROXIMATE, SEE NOTICE IN LEGEND

SCALE: 1 " = 1,000 '

0 1,000 2,000 3,000 Feet

CHART NO. 100

RIVER MILE 296.4 TO 299.4