# **BRANDON ROAD INTERBASIN PROJECT**



### STRUCTURAL PLAN FEATURES

**Engineered Channel:** Creates a concrete channel without fish habitat. Increases the effectiveness and reduces the impacts of some measures and is a platform for future technologies.

**Electric Deterrent:** Creates an electric field that deters fish.

Automated Barge Clearing (ABC) Deterrent: Bubble curtain removes small and stunned fish entrained in spaces between barges.

Acoustic Fish Deterrents: Underwater sounds to deter fish.

**Bubbler Deterrent:** Bubble curtain that deters fish.

Support Facilities: Infrastructure to support operations and maintenance of controls.

Boat Launches: Provides access for nonstructural measures, safety and future operation and management.

### RISK-INFORMED AQUATIC NUISANCE SPECIES CONTROL STRATEGY

The Recommended Plan developed during the feasibility phase of this project uses integrated aquatic nuisance species management to maximize the effectiveness of the aquatic nuisance species control system while minimizing impacts to navigation. Success requires shared responsibility.

#### **Future without Project**

- Continued operation of the Chicago Sanitary and Shipping Canal (CSSC) **Electric Deterrent**
- Continued monitoring, overfishing, public education and research, etc.

#### **Nonstructural Controls**

- Monitoring aquatic nuisance species populations
- Increased overfishing to reduce population pressure at Brandon Road.
- Maximizes effectiveness of the aquatic nuisance species management system

#### **Structural Controls**

- Flushing Lock
- Electric Deterrent
- Acoustic Fish Deterrent
- Fish Entrainment Deterrent

#### **Importance of Engineered Channel**

- Increases effectiveness of aquatic nuisance species controls
- Improves underwater monitoring
- Reduces stray current impacts of the electric deterrent
- Increases effectiveness of fish clearing within the channel
- Provides platform to test & implement future aquatic nuisance species controls



# Two control points

- CSSC Electric Deterrent
- Brandon Road control point

#### Three management zones

- Population Reduction Zone: monitoring and harvesting
- Monitoring, Management and Control Zone
- Monitoring and Response Zone

# **Shared responsibility**


# PRE-CONSTRUCTION, ENGINEERING & DESIGN

# **Value Engineering with Design Charrettes**

- Overall Project Design
- Engineered Channel
- Flushing Lock
- Aquatic Nuisance Species Controls
- Site Preparation and Support Buildings

#### Goals

- Assess Possible Efficiencies in Design and Construction Methods
- Maximize Aquatic Nuisance Species Control Effectiveness
- Minimize navigation impacts by Evaluating Construction Methods and Timing, and Coordination with Navigation Community



# **BRANDON ROAD INTERBASIN PROJECT**



# **FY23 Scheduled Activities**

- PPA Negotiations
- Complete all remaining ERDC R&D efforts
- Complete Certified Cost Estimate: 10 MAR
- Increment I-A Design 95%: 23 JUN
- Increment I-A Design 100%: 30 SEP
- Initiate Scoping for I-B and II contracts

# **BRIP FY23-25 SCHEDULED ACTIVITIES OVERVIEW**

#### **FY24 Planned Activities**

PPA Executed

**Electrical Arrays** 


- Fabrication Contract (Speakers)
- Construction Contract Increment I-A
- Complete Designs of Increment I-B
- Initiate Construction of Increments I-A
- Initiate Design of Increment II

### **FY25 Planned Activities:**

- Continuation of Increment I-A Construction
- Continuation of Design of Increment II
- Construction Contract for Increment I-B
- Initiate Fabrication of New Lock Gates
- Initiate Const. of Flushing Lock (Phase 1 of 3)







# **Channel Rock Excavation**

Upstream Boat Launch

**INCREMENT I-A** 

**INCREMENT I-B** 

Site Prep

• Electric Deterrent

**INCREMENT II** 

- Wide Acoustic Deterrent Array
- Complete Control Building
- RDB Wall Connect to Lower Guidewall

**PROPOSED INCREMENTS** 

• Automated Barge Clearing (ABC) Deterrent

Leading Edge Acoustic Deterrent Array

Leading Edge Bubble Deterrent

Leading Edge Support Facilities

- Flushing Lock
- Downstream Boat Launch

# **INCREMENT III**


Finish Engineered Channel

Total Project Costs: \$1.146B\* \*Based on FY23 price levels

ESTIMATED PROJECT COSTS	
Contributor	Estimated Total Project Costs <sup>a</sup>
Total Federal Contribution (90%)	\$1,031,483,700
Total Non-Federal Contribution (10%)	\$114,609,300
Cash	\$113,225,300
Lands, Easements, Right-of- Ways, Relocations & Disposal (LERRDs)	\$1,384,000
Total Project Costs	\$1,146,093,00
Nonstructural Measures (Equiva	alent Average Annual Cost) <sup>b</sup>
Project Cost	
USACE (80%)	\$478,08
Non-Federal Sponsor (20%)	\$119,52
Not Project Costs	
Department of the Interior	\$14,130,00
Total Nonstructural Measures	\$14,727,60
Operation, Maintenance, Repairs, Rehal (Equivalent Averag	
USACE (100%) flushing lock	\$33,50
USACE (80%)	\$7,681,44
Non-Federal (20%)	\$1,920,36
Total OMRR&R	\$9,635,30

estimated using a base year of FY 2024 and a 50-year period of analysis. b) Nonstructural measures are assumed to 80% Federal and 20% non-Federal, c) OMRR&R activities are assumed to commence in FY29. Pursuant to Water Resourc nt Act of 2018, H.R. 3021, 115th Cong. § 1142 (2018) OMRR&R costs are 100%





# **BRANDON ROAD INTERBASIN PROJECT**



